



SHEET GENERAL NOTES

- SEE APPLICABLE NOTES ON SHEET P001.
- KITCHEN EQUIPMENT FURNISHED BY OWNER UNLESS OTHERWISE NOTED. PROVIDE ALL APPURTENANCES AS NECESSARY FOR COMPLETE INSTALLATION. SEE ARCHITECTURAL DRAWINGS FOR ADDITIONAL INFORMATION.
- CEILING SPACE IS LIMITED. FIELD VERIFY EXISTING CONDITIONS AND COORDINATE ALL WORK PRIOR TO INSTALLATION.
- CEILING SPACE SERVES AS A RETURN AIR PLENUM. ALL MATERIALS USED MUST MEET 25 FLAME SPREAD AND 50 SMOKE DEVELOPMENT RATING. SEE SPECIFICATIONS FOR INSULATION REQUIREMENTS.

SHEET KEY NOTES

- 3/4" CW DOWN TO WATER TREATMENT SYSTEM TO SERVE COMBI OVENS. PROVIDE 3/4" RP-1 PRIOR TO WATER TREATMENT SYSTEM. INSTALL WATER TREATMENT SYSTEM, HYDRO PNEUMATIC TANK, AND PIPING KIT FURNISHED BY KITCHEN EQUIPMENT VENDOR. SEE DETAIL 11P501.
- SEE DETAIL 6P501. CONNECT HOT WATER RETURN TO HOT WATER PIPING 12 INCHES ABOVE FINISHED FLOOR.
- SEE DETAIL 4P501.
- OB-1. MOUNT BOTTOM OF OUTLET BOX AT 2" ABOVE TOP OF COUNTER. OUTLET BOX TO BE CONCEALED BEHIND BEVERAGE DISPENSER. COORDINATE BEVERAGE DISPENSER LOCATION WITH ARCHITECTURAL DRAWINGS.
- 3/4" CW DOWN. 3/4" CW TO KS-1. 1/2" CW TO POT FILLER PROVIDED BY OWNER. INSTALLED BY PLUMBING CONTRACTOR. 1/2" CW & 1/2" HW TO KS-2 IN ISLAND. PROVIDE STAINLESS STEEL ESCUTCHEON AT PENETRATION OF BACK SUPPLY PLENUM.
- PROVIDE 3/4" COLD WATER CONNECTION TO DISHWASHER. PROVIDE 3/4" COLD WATER TO 3/4" RP-1. INSTALL DRAIN TEMPERING KIT (FURNISHED BY OWNER) DOWNSTREAM OF 3/4" RP-1 ON DISHWASHER INDIRECT WASTE LINE. SEE DETAIL 16P501.
- INSTALL WATER FILTER ON WALL NEXT TO ICE MACHINE AND INSTALL 1/2" FILTERED WATER CONNECTION. SEE DETAIL 15P501.
- 3/4" RO WATER FROM WATER TREATMENT SYSTEM TO COMBI OVENS. PROVIDE STAINLESS STEEL PIPING WITH PRESS-FIT JOINTS AND STAINLESS STEEL VALVES FOR ALL REVERSE OSMOSIS WATER PIPING PER SPECIFICATION SECTION 221116.
- 4" VENT AND FLUE FROM WATER HEATER UP TO CONCENTRIC VENT KIT. TERMINATE CONCENTRIC VENT KIT THRU ROOF. MAINTAIN A MINIMUM SEPARATION OF 15' BETWEEN KITCHEN MAKE UP AIR UNIT INTAKE AND CONCENTRIC VENT TERMINATION.
- SEE DETAIL 5P501.
- SEE DETAIL 8P501 FOR TYPICAL WATER FILTER ARRANGEMENT.

REVISIONS

NO.	DATE	DESCRIPTION
1	2/13/2020	ADDENDUM #1
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		

DATE 1-6-20	JOB NO. 50-1414-19
DWG BY AMK	CHECKED BY JRO

SHEET TITLE
ENLARGED
DOMESTIC
WATER FLOOR
PLAN

PRELIMINARY DWGS. ☐
FINAL CONST. DWGS. ☒

SHEET NUMBER

P202

PLUMBING



KEY PLAN
NOT TO SCALE



ENLARGED DOMESTIC WATER PLAN
1/4" = 1'-0"