SHEET GENERAL NOTES

1. SEE APPLICABLE NOTES ON SHEET h001.
2. KITCHEN EQUIPMENT FURNISHED BY OWNER UNLESS OTHERWISE NOTED. SEE ARCHITECTURAL DRAWINGS FOR ADDITIONAL INFORMATION.
3. KITCHEN HOOD EXHAUST DUCTWORK SHALL BE PITCHED, SLOPE TOWARD HOOD.
4. APPLY FIRE-RATED INSULATION SYSTEM ON ENTIRE DUCT FROM HOOD KH-1, TO ASSOCIATED EXHAUST FAN.
5. CEILING SPACES ABOVE OFFICE AREAS TO BE USED AS A RETURN AIR PLENUM.

KEY NOTES

1. DUCT SHALL TRAVEL IN JOIST SPACE OVER SUPPLY MAIN. FIELD VERIFY EXISTING CONDITIONS.
2. 36X20 RETURN OPENING IN TOP OF DUCT.
3. 18x32 SUPPLY AND 18x32 RETURN UP TO ROOF TOP UNIT. INSTALL DUCT SMOKE DETECTOR FURNISHED BY ELECTRICAL CONTRACTOR AND PROVIDE WIRING TO SHUTDOWN UNIT. WIRING TO FIRE ALARM SYSTEM BY ELECTRICAL CONTRACTOR.
4. DIRECT SLOT DIFFUSERS TO WASH WINDOW SURFACE.
5. 26x68 SUPPLY AND 20x76 RETURN UP TO ROOF TOP UNIT. INSTALL DUCT SMOKE DETECTOR FURNISHED BY ELECTRICAL CONTRACTOR AND PROVIDE WIRING TO SHUTDOWN UNIT. WIRING TO FIRE ALARM SYSTEM BY ELECTRICAL CONTRACTOR.
6. 36x42 SUPPLY UP TO KITCHEN MAKE-UP AIR UNIT. SEE DETAIL 3/H501. INSTALL DUCT SMOKE DETECTOR FURNISHED BY ELECTRICAL CONTRACTOR AND PROVIDE WIRING TO SHUTDOWN UNIT. WIRING TO FIRE ALARM SYSTEM BY ELECTRICAL CONTRACTOR.
7. 22x22 EXHAUST UP TO EXHAUST FAN ON ROOF. SEE DETAIL 1/H501.
8. VARIFLOW CONTROL CABINET.
9. 12x12 EXHAUST UP TO EXHAUST FAN ON ROOF. SEE DETAIL 4/H501.
10. FIRE SUPPRESSION CABINET.
11. 16x10 SUPPLY CONNECTION TO PLENUM. TYPICAL OF 6 (585 CFM).
12. TF-1: EXHAUST FAN TO DISCHARGE TO PLENUM SPACE.
13. 50x40 RETURN OPENING IN TOP OF RETURN DUCT.
14. 18x10 SUPPLY CONNECTION TO PLENUM. TYPICAL OF 2 (650 CFM).
15. 24x24 TRANSFER OPENING ABOVE LAY-IN CEILING.
16. 14x14 EXHAUST CONNECTION TO KITCHEN HOOD.
17. 16x14 EXHAUST CONNECTION TO KITCHEN HOOD.
18. TOUCH SCREEN CONTROL PANEL FOR KITCHEN VENTILATION SYSTEM.
19. THROUGH WALL TRANSFER SLEEVE. PROVIDE 12x36 RG-2 ON EACH SIDE OF TRANSFER OPENING.

ENLARGED HVAC FLOOR PLAN

1/4" = 1'-0"

NORTH

KEY PLAN

NOT TO SCALE



ESI
ARCHITECTURAL & ENGINEERING SERVICES INC.
SMART BUILDING SOLUTIONS
Arch. Bus. Lic. Nbr. AA26001599
Eng. Bus. Lic. Nbr. 28045
950 Walnut Ridge Drive | Hartland, WI 53029 | 262.369.3535 T | 262.369.3592 F

US FOODS

KITCHEN RENOVATION FOR
US FOODS - SOUTH FLORIDA
7598 NW 6TH AVENUE
BOCA RATON, FL 33487

REVISIONS

1	2/7/2020 – ADDENDUM #1	
	-	
	-	
	-	
	-	
	-	
	-	
	-	
	-	
	-	

DATE	JOB NO.
1-6-20	50-1414-19
DWG By: AMK	CHK'D By: JRO

SHEET TITLE

ENLARGED HVAC FLOOR PLAN

PRELIMINARY DWGS.
FINAL CONST. DWGS. ■

SHEET NUMBER

H201

HVAC