



GENERAL NOTES

1. SEE APPLICABLE NOTES ON SHEET E001.

KEY NOTES - THIS SHEET ONLY

1. SEE SKC COMMUNICATIONS AV DRAWINGS FOR ROUGHIN REQUIREMENT LOCATIONS FOR ALL AV EQUIPMENT.
2. DOOR CONTACT FOR ROOF HATCH.
3. INSTALL PVC CONDUIT UNDER SLAB FOR ALL CIRCUITS FROM CENTER CABINETS TO INSIDE NEAREST WALL. TRANSITION TO EMT CONDUIT INSIDE WALL. RUN CONDUIT UP WALL TO ABOVE CEILING.
4. INSTALL PVC CONDUIT UNDERGROUND FOR ALL FLOOR BOXES. TRANSITION TO EMT CONDUIT INSIDE WALL. RUN CONDUIT UP WALL TO ABOVE CEILING. TYPICAL OF 12.
5. INSTALL PVC CONDUITS (ONE FOR POWER AND ONE FOR DATA) TO NEAREST WALL. TRANSITION TO EMT CONDUIT INSIDE WALL. RUN CONDUIT UP WALL TO ABOVE CEILING. TYPICAL OF TWO.
6. FIRE SUPPRESSION CABINET PROVIDED BY MECHANICAL CONTRACTOR. SEE DETAIL 2 ON THIS SHEET.
7. PROVIDE FIRE ALARM SMOKE DETECTOR FOR SUPPLY AND DISCHARGE AIR, RTU, GFCI RECEPTACLE IS MOUNTED ON ROOF.
8. PROVIDE FIRE ALARM SMOKE DETECTOR FOR SUPPLY AIR. SMOKE DETECTOR TO FIRE ALARM SYSTEM AND PROVIDE A SET OF CONTRACTS FOR KLU+ SHUTDOWN WIRED BY MECHANICAL CONTRACTOR. COORDINATE LOCATION WITH MECHANICAL CONTRACTOR.
9. ALL PANELS IN ROOM B108 ARE EXISTING.

ESI ARCHITECTURAL &
ENGINEERING
SERVICES INC.
SMART BUILDING SOLUTIONS
Arch. Bus. Lic. Nbr. A626001599
Eng. Bus. Lic. Nbr. 28045

950 Walnut Ridge Drive | Hartland, WI 53029 | 262.369.3535 T | 262.369.3592 F



KITCHEN RENOVATION FOR
US FOODS - SOUTH FLORIDA
7598 NW 6TH AVENUE
BOCA RATON, FL 33487

REVISIONS

[illegible]

DATE 1-6-20	JOB NO. 50-1414-19
DWG By. EGP	CHK'D By. TJM

SHEET TITLE

POWER AND
SYSTEMS PLAN

PRELIMINARY DWCS |

PRELIMINARY DWG.

FINAL CONST. DWGS.

E211
